

VOYAGE2007



Piloting a Centralized Remedial Action Scheme (C-RAS) with Emerging Telecomm / Protection Technologies

Patricia Arons
Transmission & Interconnection Planning
Southern California Edison Company




SCE T&D Assets

Generation

Transmission & Subtransmission

Distribution

Customer




Note: Data as of year-end 2005


SCE Transmission Network

Key Transmission Planning/ Operational Issues

- **Congested transmission corridors/
network**
 - ▶ Ever increasing customer load growth
- **Long lead time to build transmission**
 - ▶ Transmission lagging generation and customer load growth
- **Integration of new generators
including renewables into the
transmission network**
 - ▶ Uncertainty on new generation siting/locations
 - ▶ Legislative/regulatory renewable targets mandate
- **Increasing transmission voltage
support requirements**
- **Extensive use of “Remedial Action
Schemes (RAS)”**



SCE Transmission Corridors and Proliferating RAS Schemes




- Existing RAS = 17 on all transmission corridors
- Expected potential new RAS (2007-2009) = 28
- RAS impacted transmission
 - ▶ Generation tripping
 - ▶ Load shedding

Voltage	Miles of Transmission Circuits	
	Total Miles	RAS Monitored (%)
500 kV	1,183	1,069 (90% of mi.)
230 kV	3,574	1,181 (33% of mi.)
115 kV	1,846	350 (19% of mi.)
All	6,603	2,600 (40% of mi.)

Key Observation: Almost all bulk power lines bringing generation / imports into the greater Los Angeles basin load area are being monitored for contingencies and flow levels, and controlled by local RAS schemes.

RAS Timeline

A RAS Case Simulation



1 cycle = 16.7 milliseconds

	Time	Operational Events
Step 1	@ 0 Cycle	3 Phase Fault on the Bus
Step 2	@ 1 Cycle	Relay Processing time for trip signal to CBs
Step 3	@ 5 Cycles	Open CBs for line/transformer out
Step 4	@ 7 Cycles	RAS Logic Processing for trip signal to CBs to trip generators
Step 5A	@ 10 Cycles	Open CBs associated with 12 generators (I Batch Mitigation)
Step 5B	@ 12 Cycles	Open CBs associated with 4 generators (II Batch Mitigation)
Step 5C	@ 16 Cycles	Open CBs associated with 2 generators (III Batch Mitigation)

Event Detection Fault Clearing:

5 Cycles

RAS Processing:

2 Cycles

Mitigation Generation Tripping / Load Shedding:

9 Cycles

Total Elapsed Time:

16 Cycles

Key Findings and Issues with Local RAS Schemes

- **LABORIOUS:** Planning, design, programming, implementation and operational tasks
- **PROLIFERATION:** Almost all transmission network involved
- **INCREASING DEPENDENCY:** 31 new schemes identified in the Generator “Queue” (2007-2009)
- **CUSTOMIZATION:** No ability to replicate a scheme and high maintenance costs
- **ONE SIZE FITS ALL:** Inability to size mitigation targets based on dynamic assessment of generation tripping / load shedding requirements
- **OVERLAP:** Generation / Load subject to interruption for numerous reasons
- **SLOW ARMING/DISARMING:** Arming by EMS computer may take 8–16 seconds delayed signals
- **TIME LOSS:** Excessive travel time by engineering and field staff to maintain the local RAS schemes at numerous sites
- **NUMEROUS REVISIONS:** Expanding Generator “Queue” and network changes affects existing local RAS schemes
- **LOW STAFF MORALE:** The impossible problem of increasing work load, short deadlines, proliferating archaic technology and losing skilled staff (added 2 new & updated 3 RAS schemes for 2006 summer)

SOLUTION

A Centralized RAS (C-RAS) Plan

Key Requirements for C-RAS Scheme Speed Testing

A. Protection/Computing/Data Packets Over Ethernet Protocol

- | | | |
|---|---|----------|
| 1. Line Flows for Arming | → | PMU |
| 2. Line Outage Detection | → | Relay |
| 3. Logic Processing with GOOSE Data Packets | → | Computer |
| 4. Mitigation Action Signal | → | Relay |



GE N-60
Universal Relay




Capabilities:

- Synchrophasor PMU
- Outage/Mitigation relay functions
- CPU processor with GOOSE data packets

B. Telecommunication Infrastructure

- | | | |
|---|---|-----------------------------------|
| 1. Availability of Telecomm. Circuits to substations on each corridor | → | Two T1 circuits for each corridor |
| 2. Adequate Bandwidth and Speed for GOOSE Data Packets | → | T1 = 1.544 Mbps |
| 3. Network distances to be covered | → | 100 – 660 miles |
| 4. Desired Speed for C-RAS | → | < 50 ms |

Solution






Layout of the C-RAS Scheme Concept With Emerging Telecomm/Protection Technologies

I. Monitoring & Detection

1. Line flow monitoring
2. Line outage detection



II. RAS Logic Processing



C-RAS Logical Telecommunication Network

III. Mitigation

1. Generation/ load level monitoring
2. Generation tripping/load shedding mitigation



Telecomm / Protection Technologies

- Use of IEC 61850 "Goose" standard over SCE Telecomm Wide Area Network (WAN) with Ethernet switches/routers
- Use of N-60 relays (GE or other) for line outage detection & mitigation signal delivery
- Use of triple redundant Programmable Logic Controller (PLC) – Computing Processors

What is in a GOOSE?

(Generic Object Oriented Substation Event)

An IEEE approved data packet standard – IEC61850 over Ethernet protocol


```
⊕ 802.1Q virtual LAN - LAN Priority
⊖ IEC 61850 GOOSE
  AppID: 0x0000
  PDU Length: 769
  Reserved1: 0x0000
  Reserved2: 0x0000
⊖ PDU
  [APPLICATION 1] (length = 757)
  GOOSE Control Reference (length=13): mydom/mygcRef
  TimeAllowedToLive (length=1): 4 msec
  DataSet Reference (length=15): mydom/mydataset
  Application ID(length=9): testAppID
  Event Timestamp: 2004-01-06 22:10.20.000000 Timequality: 00
  State Change Number (length=1): 1
  Sequence Number (length=1): 1
  Test Mode (length=1): FALSE
  Config Rev Number (length=1): 32
  Needs Commissioning (length=1): FALSE
⊕ Num Data Entries (length=1): 3
```

GOOSE Data: Complexity is Allowed

Metered Data – Flow amps, voltages, phase angles, weather, etc.

```
DATA[002]
{
  UNSIGNED: 3
  FLOAT: 4.234000
  UNSIGNED: 5
  FLOAT: 6.234000
  UNSIGNED: 7
  FLOAT: 8.235000
  UNSIGNED: 9
  FLOAT: 10.235000
  BITSTRING:0101010101010101
  BTIME06: 2000-07-04 23:59:14.432 (days=6022 msec= 691154432)
}
```

Magunden and Inyokern Telecommunication Circuit Routes




- Microwave
- Fiber
- Communication Site (C.S.)
- Substation
- Facility
- Magunden Route
- Inyokern Route

Total Telecomm Circuit Mileage


GO-4 to Magunden:
178 miles

GO-4 to Inyokern:
220 miles

Proposed Telecomm / Protection Relay Set-Up for initial C-RAS Scheme Testing



Resolution of Issues for initial C-RAS Scheme Set-Up (Phase – 1)



N-60 Relay based Central Processors to be replaced with high Performance Computing Processors as C-RAS logic processors loaded with "Off-The-Shelf" SISCO modules and tools in Phase-2


GO-4 C-RAS Laboratory

Key Results:


- LAN Speed (local fiber within GO-4 C-RAS Lab.) = 11 - 12 ms
- WAN Speed (500 - 660 miles over SCEnet from Outage detection to Mitigation action delivery) = 20 - 22.5 ms
- Use of IEC 61850 GOOSE standard protocol using N-60 relay GOOSE capabilities

Set-Up With Off-the-Shelf SISCO Tools for C-RAS Pre-Pilot (Phase-2)

Pre-Pilot C-RAS Controller Set-Up (A High Performance Logic Computing Processor) at Alhambra/Rosemead



Transition From Pre-Pilot (Phase 2) to Pilot (Phase 3) Set-up



Detailed Scope of the C-RAS Pilot Project

The C-RAS Pilot project will comprise of the following SISCO products and services jointly with SCE:

- a. **Engineering, design, development, and installation of the following software & Controller components and provision of module license for the C-RAS Pilot project:**
 - i. High Speed GOOSE Logic Interpreter
 - ii. GOOSE Blaster
 - iii. C-RAS Analytic platform
 - iv. C-RAS Arming / Mitigation Logic Algorithms
 - v. Controller hardware boxes (Industrial strength computing processors)
 - vi. MMS – EASE Lite License
- b. **Installation, simulation, experimentation, and testing of the following key C-RAS pilot functionalities:**
 - i. High speed interface testing of configurable GOOSE data packets to achieve acceptable performance results (<50 - 60 ms) for line outage detection, logic processing, arming, and mitigation signal delivery
 - ii. C-RAS / EMS Data Exchange simulation utilizing CAISO sample network representation in coordination with EMS Power Systems Control group
 - iii. Mirror imaging and testing of one existing RAS scheme (South of Lugo RAS) Experimenting with varying RAS calculations and arming algorithms
 - iv. C-RAS Scheme Acceptance Test (SAT)
 - v. Defining and establishing demarcation points (per Chairman, WECC RAS Task Force) in the C-RAS pilot scheme set-up for diagnostics of signal errors, its resolution, and also presenting the scheme and performance results to WECC RAS Task for their review and approval per NERC / WECC RAS standards

Review of C-RAS Pilot Testing Results & Current Plan

- Phase 1 Results: Telecommunication speed measurement for generic GOOSE data packets generated from N-60 Relays to cover a distance of 500 – 600 miles over SCENet Fiber / Microwave infrastructure
 - ▶ Speed tested successfully with 21 milliseconds (< 1.3 cycles) time achieved for the following functions:
 - Line outage detection generated by N-60 relays at Magunden & Inyokern substations
 - Generic GOOSE data packet receipt by Controller (N-60 relay) and initiating RAS mitigation step
 - Sending mitigation signal for tripping generators at Magunden & Inyokern substations
- Phase 2 (Pre-Pilot) Results: C-RAS set-up with Off-the-shelf OSIssoft PI & SISCO products with an Industrial C-RAS controller replacing N-60 Relay used in Phase 1 above
 - ▶ Speed tested successfully with 40 milliseconds (<2.5 cycles) time achieved for the following functions:
 - Line outage detection generated by N-60 relays at Magunden & Inyokern substations
 - GOOSE data packet receipt, processing, and creation of GOOSE mitigation signal utilizing SISCO & OSIssoft Off-the-shelf products installed on the Controller
 - Sending mitigation signal for tripping generators at Magunden & Inyokern substations
- Phase 3 (Pilot) Plan: C-RAS set-up & testing with comprehensively developed custom products by SISCO consultants & RAS calculation module by TDBU TIP staff to measure performance
 - ▶ Capabilities to be tested: Installing C-RAS pilot system with high speed GOOSE data from multiple RAS signals, mirroring of an existing RAS scheme, operating C-RAS pilot in parallel with an existing RAS scheme, Scheme Acceptance test, Documentation, and obtaining approval of the C-RAS technologies and set-up by WECC RAS task force
 - ▶ Completion Target: – Planned completion by January 31, 2008

Potential Grid Applications and Benefits From C-RAS Implementation


- Electric System Planning / Network Engineering:
 - ▶ Enhanced transmission capacity ratings (up to 5-10%) with shrinking timeline for RAS calculations and capability to fine tune mitigation in place of fixed amounts of mitigation
 - ▶ Easier to design, deploy and maintain RAS schemes under varying seasonal and system conditions
 - ▶ Capability to deploy C-RAS based solutions to monitor and reduce the risk of system-wide voltage degradation or collapse risks / problems (AC stalling at Valley, Antelope, Rector, Villa Park and Devers substations)
 - ▶ Additional study tool for use in Transmission & Interconnection planning
- Grid Operations
 - ▶ Grid Control Center
 - Continued capability to arm / disarm a specific RAS operation via C-RAS link
 - Capability to get synchronized time – stamped power system data via C-RAS in place of 4-8 seconds of EMS Scan gaps
 - Potential of dynamic switching to change transmission line loadings
 - ▶ Substations
 - Simplified operation methods with better information
 - Improved Operator training methods

Potential Grid Applications and Benefits From C-RAS Implementation - continued

- Adoption of new Technologies and improved usage of Telecom infrastructure to reduce customer costs
 - ▶ Replacement of point – to – point wiring or channels and usage of Wide Area Network (WAN) Ethernet protocol
 - ▶ Capability to deploy redundancy in RAS schemes and to achieve improved automation in the testing of RAS schemes
 - ▶ Capability to accomplish “Bird’s eye view” of SCE grid by monitoring real-time synchronized time stamped load, generation, imports and rates of change in these power system metrics for improving operations, productivity and processes
 - ▶ Capability to implement a pioneering “Real-time Grid Monitoring System” for SCE grid following DOE / FERC approach to achieve a “Smart Grid” operation
- A tool to maintain grid reliability and safety
 - ▶ Protects SCE’s growing Transmission / Distribution investments of over \$9.5 billion (2006-’10) by reducing the risks of cascading outages leading to major brownouts and / or blackouts

Southern California Import Transmission (SCIT)


- Summer 2007 SCIT total import capability will be 16,100 MW.
 - ▶ 500 MW increase over 2006
- It is limited by the loss of two SONGS units.
- Increase due to Valley voltage support and additional generators.



SCIT Components

- Midway-Vincent
- Pacific DC
- Intermountain DC
- North of Lugo
- West of River

C-RAS Based New Grid Reliability Standards and Operations Approach



Existing Reliability Criteria Mgmt.

1. N-1 and N-2 line/transformer outages
2. Path 26 outage
3. Limited to within SCE Grid Network

Future Reliability Criteria Mgmt.

1. Impacts of disturbances in Neighboring Grid Network
 - Recent LADWP outages of DC line and loss of major load
 - Major SCIT import changes
2. Expected DOE/FERC Mandatory Reliability Standards (Aug. 2006)
 - Influence for incentives to achieve higher reliability
3. Critical N-3 outages (Going beyond N-2)
4. Fire and earthquake disaster impacts
5. Faster post disturbance load restoration

VOYAGE2007



***Thank
You***

OSISOFT

Copyright © 2007 OSISOFT, Inc. All rights reserved.

VALUE NOW, VALUE OVER TIME